

BILL OF QUANTITIES					
PREVENTIVE MAINTENANCE OF PACO PARK					
Gen. Luna and San Marcelino Sts., Manila					
Item	Description	Unit	Quantity	Unit Price	Amount
I.	PROVISION FOR TEMPORARY FACILITIES AND SCAFFOLDING				
	A.1 Provision of Field Office (Rental)	months	4.00		
	A.2 Project Billboard	l.s.	1.00		
	A.3 Scaffolding Works (Rental)				
	Rental per set				
	6 H - Frame (1.70 x 1.20) @ P /pc. = P				
	12 Cross Braces (1.80m) @ P /pc. = P				
	2 Catwalk 0.50m x 1.80m @ P /pc. = P				
	Joint Pin				
	Adjustable U- Head				
	8 pcs. x 1 1/4" x 600mm @ P = P				
	Adjustable Base Jack				
	8 pcs. x 1 1/4" x 600mm @ P = P				
	Total Amount Per set =				
	No. of Sets = 15 sets x P /Month = P	months	4.00		
	A.4 Blue Lona for Safety Barricade & Temporary	rolls	9.00		
II.	BALLUSTERS (Cleaning and Minor Repair of Existing Ballustre and Banister)				
	1. Materials (No. of Ballusters = 598 pcs.)				
	Mallet	pcs	5.00		
	Chisel (Wide, Fabricated)	pcs	10.00		
	Chisel (Narrow, Fabricated)	pcs	10.00		
	Anvil for chisel fabrication	pcs	1.00		
	Sand (sieved)	sacks	100.00		
	Slaked Lime Putty	drums	7.00		
	Nylon Brush	pcs.	50.00		
	Garden Hose with nozzle (1" dia. @ 20m)	set	1.00		
	Crushed Potted Clay	sacks	5.00		
	Trowel	pcs.	10.00		
	Concrete Float	pcs.	10.00		
	Shovel Flat (Metal)	pcs.	5.00		
	Shovel Pointed (Metal)	pcs.	5.00		
	2. Labor Cost				
	1 - Foreman @ /day	days	9.00		
	20 -Stone Masons @ /day =	days	9.00		
III.	CHAPEL WALLS (Rehabilitation/Repair of the Chapel Walls) *EXTERIOR				
	1. Materials (Area = 325 m <sup>2</sup> )				
	Adobe Block (15"x35"x15")	pcs.	45.00		
	Mallet	pcs.	10.00		
	Chisel (Wide, Fabricated)	pcs.	20.00		
	Chisel (Narrow, Fabricated)	pcs.	20.00		
	Anvil for chisel fabrication	pcs.	1.00		
	Sledge Hammer (6lbs)	pcs.	20.00		
	Angle Grinder	pcs.	2.00		
	Grinder Blades (cutting)	pcs.	50.00		
	L-Square 36"	pcs.	5.00		
	Sand (sieved)	sacks	200.00		
	Slaked Lime Putty	drums	10.00		
	Crushed Potted Clay	sacks	2.00		
	Stainless Steel Round Bar No 10 (6mts.)	pcs.	3.00		
	Charcoal	sacks	3.00		
	2. Labor Cost				
	1 - Foreman @ /day	days	12.00		
	20 -Stone Masons @ /day =	days	12.00		

Item	Description		Unit	Quantity	Unit Price	Amount
IV.	OSSUARY (Cleaning and Minor Repair) *COURT B (Area = 127.72 m <sup>2</sup> )					
	1. Materials					
		Nylon Brush	pcs.	50.00		
		Garden Hose with nozzle (1" dia. @ 20m)	set	1.00		
		Paint Brush 4"	pcs.	10.00		
		Paint Brush 2"	pcs.	10.00		
		Slaked Lime Putty	drums	1.00		
		Latex Paint (Yellow Ocre)	liters	10.00		
	2. Labor Cost					
		1 - Foreman @ /day	days	3.00		
		20 -Stone Masons @ /day =	days	3.00		
V.	PILASTERS (Cleaning and Repair)					
	1. Materials (No. of Pilaster = 128 pcs.)					
		Mallet	pcs	10.00		
		Chisel (Wide, Fabricated)	pcs	20.00		
		Chisel (Narrow, Fabricated)	pcs	20.00		
		Anvil for chisel fabrication	pcs	2.00		
		Sand (sieved)	sacks	500.00		
		Slaked Lime Putty	drums	15.00		
		Crushed Potted Clay	sacks	5.00		
		Trowel	pcs.	20.00		
		Concrete Float	pcs.	10.00		
		Shovel Flat (Metal)	pcs.	5.00		
		Shovel Pointed (Metal)	pcs.	5.00		
	2. Labor Cost					
		1 - Foreman @ /day	days	12.00		
		10 -Stone Masons @ /day =	days	12.00		
VI.	REMOVAL OF PLANT GROWTHS WITH STONE REPAIRS					
		Outer Circle (Area = 2,144.99 m <sup>2</sup> )				
		Inner Circle (Area = 1,280.75 m <sup>2</sup> )				
	1. Materials					
		Adobe Block (15"x35"x15")	pcs	465.00		
		Re-pointing tool fab	pcs	55.00		
		Level Bar (24in)	pcs	13.00		
		Plumb bob	pcs	6.00		
		Nylon Strings	lot	1.00		
		Adobe Block (20"x 40"x18")	pcs.	100.00		
		Lime Putty	drums.	30.00		
		Sand (sieved)	sacks.	500.00		
		2"x2"x8' S4S Lumber	pcs	30.00		
		Assorted nails	lot.	1.00		
		Syringe (5ml)	pcs.	50.00		
		Rubber bands	lot.	1.00		
		Heavy duty cutter	pcs.	30.00		
		Herbicide	gals.	10.00		
	2. Labor Cost					
		1 - Foreman @ /day	days	24.00		
		20 -Stone Masons @ /day =	days	24.00		
VII.	CLEANING OF WALLS					
		Outer Circle (Area = 2,144.99 m2)				
		Inner Circle (Area = 1,280.75 m2)				
		Ossuary Court A (Area = 256.60 m2)				
		Ossuary Court B (Area = 185.40 m2)				
	1. Materials					
		Nylon Brush	pcs.	50.00		
		Garden Hose with nozzle (1" dia. @ 20m)	set	1.00		
		Paint Brush 4"	pcs.	10.00		
		Paint Brush 2"	pcs.	10.00		
		Slaked Lime Putty	drums	2.00		
		Latex Paint (Yellow Ocre)	liters	10.00		
	2. Labor Cost					
		1 - Foreman @ /day	days	24.00		
		20 -Stone Masons @ /day =	days	24.00		

Item	Description		Unit	Quantity	Unit Price	Amount
VIII.	GENERAL REPOINTING					
		Outer Circle (Area = 2,144.99 m <sup>2</sup> )				
		Inner Circle (Area = 1,280.75 m <sup>2</sup> )				
	1. Materials					
		Re-pointing tool fab	pcs	55.00		
		Level Bar (24in)	pcs	13.00		
		Lime Putty	drums	50.00		
		Sand (sieved)	sacks	600.00		
	2. Labor Cost					
		1 - Foreman @ /day	days	46.00		
		20 -Stone Masons @ /day =	days	46.00		
IX.	WALKWAYS (Cleaning and Minor Repairs) (Area =7,586.00 m2)					
	1. Materials					
		Bricks (Replacement)	pcs	784.00		
		Nylon Brush	pcs.	50.00		
		Garden Hose with nozzle (1" dia. @ 20m)	set	1.00		
		Mallet	pcs	10.00		
		Chisel (Wide, Fabricated)	pcs	10.00		
		Chisel (Narrow, Fabricated)	pcs	10.00		
		Anvil for chisel fabrication	pcs	2.00		
		Sand (sieved)	sacks	100.00		
		Slaked Lime Putty	drums	10.00		
		Crushed Potted Clay	sacks	5.00		
		Trowel	pcs.	10.00		
		Concrete Float	pcs.	5.00		
		Shovel Flat (Metal)	pcs.	5.00		
		Shovel Pointed (Metal)	pcs.	5.00		
	2. Labor Cost					
		1 - Foreman @ /day	days	6.00		
		20 -Stone Masons @ /day =	days	6.00		
TOTAL PROJECT COST						

Name of Company

BY :

Signature of Authorized Representative

Name of Authorized Representative